
Failed Bridges

Case Studies, Causes and Consequences

Joachim Scheer

Contents

Foreword	V
Contents	VII
Preface to the English edition 2010	XI
Preface to the German edition 2000	XIII
1 Introduction	1
1.1 Retrospect	1
1.2 Aim	3
1.3 Structure	4
1.3.1 General information about the tables	4
1.3.2 Structures included	4
1.3.3 Causes considered	4
1.3.4 Sections of the book	4
1.3.5 Sources used	4
1.3.6 Abbreviations	5
1.3.7 Overview of failure cases	6
1.4 Earlier publications on the failure of load-bearing structures	6
1.5 Estimated numbers of bridges in Germany and USA	10
2 Failure of bridges, general information	13
3 Failure during construction	15
3.1 General observations	15
3.2 Buckling of compression members in truss bridges	46
3.3 Deflection of steel compression struts or chords out of the plane of a truss or beam - a trough bridge problem	49
3.4 Failure of steel bridges with box girders	51
3.5 Failure of cantilever prestressed concrete bridge beams	62
3.6 Failure of bridges constructed by incremental launching [54]	65
3.7 Collapse of the Frankenthal Rhine bridge	69
3.8 Damage during construction of the Heidingsfeld motorway bridge	74
3.9 Failure during demolition or reconstruction	76
3.10 Remarks on cantilever erection	82
3.11 Remarks on the collapse of a steel truss bridge over the Mississippi (Case 3.103)	82
4 Failure in service without external action	85
4.1 General observations	85
4.2 Remarks on the Nienburg "cable"-stayed bridge over the River Saale, Case 4.87	115
4.3 Failure of suspension bridges	116
4.4 Collapse of the Dee Bridge	121
4.5 Collapse due to wind action, excluding suspension bridges	122
4.6 Collapse through overload, excluding suspension bridges	122
4.7 Collapse of the Mönchenstein Bridge (Case 4.28)	123

4.8	Collapse or damage due to material defects: brittle fracture	124
4.9	Damage resulting from fatigue or bad maintenance	127
4.10	Collapse of the Elbow Grade Bridge (Case 4.48)	128
4.11	Collapse of the Connecticut Turnpike Bridge over the Mianus River and the Sungsu truss bridge over the Han River in Seoul	130
5	Failure due to impact of ship collision	133
5.1	General observations	133
5.2	Conclusions from Table 5	152
6	Failure due to impact from traffic under the bridge	155
6.1	General observations	155
6.2	Impact due to failure to observe the loading height	155
6.3	Collision with bridge supports by derailed trains or vehicles leaving the road	161
7	Failure due to impact from traffic on the bridge	165
8	Failure due to flooding, ice floes, floating timber and hurricane	173
9	Failure due to fire or explosion	191
10	Failure due to seismic activity	203
11	Failure of falsework	209
11.1	General observations	209
11.2	Failure due to inadequate lateral stiffness	227
11.2.1	Inadequate ensuring of the assumed effective length of supports	227
11.2.2	Inadequate lateral bracing of compressed upper flanges of temporary beams	228
11.2.3	Inadequate bracing in the area of screw jack spindles	230
11.2.4	A special case	233
11.3	Failure due to poor foundations	234
11.4	Failure due to inadequate coordination between design and construction	238
11.4.1	Laubach valley viaduct near Koblenz. 1972, Case 11.17	238
11.4.2	Bridge near St. Paul, Minnesota, 1990, Case 11.38	241
11.5	Failure due to errors in design, construction and operation	243
11.5.1	Single-span bridge over railway tracks near Weinheim. 1967, Case 11.10	243
11.5.2	22-span bridge. 1991, Case 11.40	244
11.5.3	Working scaffolding for repair of the sidewalk parapet of a viaduct 1993, Case 11.43	244
11.5.4	Bridge at Diez near Limburg. 1997, Case 11.47	245
11.5.5	Brief descriptions	248
11.6	Three particular cases	250
12	Lessons for the practice	255
12.1	General observations	255
12.2	Design	255
12.2.1	Selection of designers	255
12.2.2	Head of design with full responsibility: chief engineer	256
12.2.3	Time and resources	258

12.2.4	Changes in the design concept or change of designers	259
12.2.5	Design of robust structures	259
12.2.6	Design of simple structures	261
12.2.7	Summaries in literature	262
12.3	Structural safety calculations and design detailing	262
12.3.1	The danger of extrapolation :	262
12.3.2	Organization: coordination, delegation, exchange of information	265
12.3.3	Verification of structural safety	266
12.3.4	Constructive design	270
12.4	Construction management	273
12.4.1	The present situation	273
12.4.2	Precautionary measures	273
12.4.3	Rules for the avoidance of risks in construction management	276
12.5	Inspection and maintenance of structures	277
12.6	Rules and formulations in engineering literature	277
12.7	My own summary	280
12.7.1	For the entire construction process	280
12.7.2	Design	281
12.7.3	Verification of structural safety	281
12.7.4	Design of details	282
12.7.5	Construction management	282
13	Lessons for teaching	283
14	Literature	285
15	Geographical Index	291
16	Sources of drawings and photographs	301
17	Index	305